

All India Institute of Medical Sciences Bhopal
Saket Nagar, Bhopal, MP- 462024

Notice Inviting Quotation

No.6007 /UG Boys Kitchen Civil Work/EE(C)/AIIMS/BPL/2013-14/11 Date 28.02.2014

On behalf of Director AIIMS Bhopal. Sealed quotations are invited by the **Executive Engineer (Civil)**, AIIMS, which will be received at the above office, from experienced Civil Contractor who have been done similar type of works.

Name of Work: - Construction work providing & laying civil work (like brick work, concrete work, ceramic tile work etc) and plumbing work in ground floor of U.G. men's hostel building.

Estimated Value of work : **Rs. 92212/-**
Period of Completion : **15 Days**
Earnest money Deposit : **Rs. 1850/-**
Quotation Submission Date : **08.03.2014 (2:00 P.M.)**
Quotation Opening Date : **08.03.2014 (3:00 P.M.)**

Sl. No.	Description	Qty.	Unit	RATE	Amount
1.	Providing and laying cement concrete in retaining walls, return walls, (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc. up to floor five level, excluding the cost of centering, shuttering and finishing :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) (Cement ACC, Birla, Bangur, Jaypee)	0.63	CUM		
2	Thermo-Mechanically Treated bars (SAIL ,TATA,RINL)	7.22	KG		
3	Small lintels not exceeding 1.5 m clear span, moulding as in cornices, window sills, string courses, bands, copings, bed plates, anchor blocks and the like	0.51	SQM		
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)(Cement ACC, Birla, Bangur, Jaypee) Extra for providing and placing in position 2 Nos 6 mm dia M.S bars at third course of half brick masonry.	41.20	SQM		
5	Extra for providing and placing in position 2 Nos 6 mm dia M.S bars at every third course of half brick masonry.	41.20	SQM		

6	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations, of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Raj Nagar Plain white marble / Udaipur green marble / Zebra black marble Area of slab upto 0.50 sqm	1.26	SQM		
7	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.(BELL, Somsny, Jonhson, Kajaria, Orient pattion as exiting tiles)	68.42	SQM		
8	12 mm cement plaster of mix: 1:4 (1 cement : 4 coarse sand)	16.42	SQM		
9	Providing and applying plaster of pairs putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	16.42	SQM		
10	Distemping with oil bound washable manufacture to give an even shade : New work (two or more coats) over and including priming coat with water thinkable distemper of approved brand and cement primer (Berger,Asian,Narolac)	16.42	SQM		
11	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings, with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc. 15 mm nominal outer dia pipes (Flowguard/Astral, Ajay, Supreme)	39.80	RM		
12	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15 mm nominal bore (Jaquar, Marc, Plumber, Kingston)	4	EACH		

Terms & Conditions:

1. The quotations must be submitted in a sealed envelope duly mentioning the NIQ number and name of the work.
2. Time is the essence of the contract.
3. **PAYMENT TERMS:-** Payment shall be released after the successful completion of work of the items and receipt of bill after deducting TDS as per Income tax Rules and any other deductions as per Government rules. **PAYMENT WILL BE MADE AFTER COMPLETION OF THE WORK**, subject to submission of Performance Guarantee for 10% value of the order. This guarantee shall be in the form of Deposit at Call receipt of any scheduled bank / Banker's cheque / Demand Draft / Pay order of any Scheduled Bank or Government Securities or Fixed Deposit Receipts or Guarantee Bonds of any Scheduled Bank in accordance with the prescribed form

valid for 6 (SIX) MONTHS. OTHERWISE 90% PAYMENT WILL BE RELEASED AFTER WORK & BALANCE 10% PAYMENT / (or Performance guarantee if submitted) WILL BE RELEASED AFTER 3 (THREE) MONTHS after full satisfaction of under signed. If the successful bidder desires then the EMD be adjusted against performance guarantee.

4. Payment shall be made through Account Payee Cheque or Electronic Clearing System only and the charges shall be deducted from the bill.
5. Tenderers may please note that they shall follow the safety and security procedures while at work in AIIMS as per the Institute's norms
6. Tenderers may please note that the work should be executed as per the standard specification and the measurements shall be recorded CPWD accordingly.
7. The work shall be carried out as per standard specifications of CPWD relevant IS code if the CPWD specification are silent and also as per manufacturers specifications as directed by Engineer-In-Charge.
8. If the contractor fails to maintain the required progress or to complete the work and clear the site on or before the expiry of contract period he shall on account of such breach, pay agreed compensation at ½% of the value of the work per week subject to maximum of 10% of tendered value of work.
9. AIIMS does not bind itself to accept the lowest or any other quotation, and reserves the authority to reject any or all of the quotations or to allot part of the works to different agencies without assigning any reason thereof. All quotations, in which any of the prescribed conditions is not fulfilled or the agencies put any condition not acceptable to AIIMS; Bhopal including that of conditional rebate is liable to be summarily rejected.
10. The quotation must be quoted duly typed on the letter heads of the supplier / manufacturer duly mentioned full address, VAT No. / PAN No. / TDS No. / TIN No. and must be in a sealed cover which should be superscribed Quotation for "Name of work".

Yogesh Purswani
Executive Engineer (Civil)